
BTO Program Peer Review



Demonstration of the effect

To develop a novel, low-cost window coating to double daylight penetration to offset lighting energy use



Problem Statement: PNNL is developing a novel, low-cost window coating to redirect daylight deeper into buildings to significantly offset lighting energy.

Impact of Project: A successful daylighting coating with high market penetration has potential for 0.4 Quad/yr lighting energy savings with an associated CO_2 offset of 7 Mtons/yr at \$2-3/ft².

Project Focus: The development of the daylighting coatings aligns with BTO goals by focusing on bringing to market a novel emerging technology with potential for savings of approximately 50% of lighting energy in commercial buildings*.

^{*}Arasteh, D.S., Steve; Apte, Josh; LaFrance, Marc, *Zero Energy Windows.* Proceedings of the 2006 ACEEE Summer Study on Energy Efficiency in Buildings, 2006.

ENERGY Energy Efficiency & Renewable Energy

Approach: The goal is to demonstrate a low-cost, scalable, high performance light-redirecting coating. PNNL employs a synergistic fabrication, modeling, and characterization approach for rapid progress.

Key Issues:


- High coating performance for light redirection (30-60% light redirection)
- Broad wavelength coating response
- Scalability and cost
- **Distinctive Characteristics:**
- Unique window coating instead of mirrors or light shelves
- Novel sub-wavelength coating features

Approach – Current SOA Daylighting

U.S. DEPARTMENT OF

Energy Efficiency & Renewable Energy

- Current daylighting technologies are expensive/ bulky/ non viewable
- Not widely adopted
- Energy savings not realized
- Need low-cost films like Low-E to improve market impact
- PNNL Nanolens coating addresses these issues



Kischkoweit-Lopin, M., An overview of daylighting systems. Solar Energy, 2002. 73: 77.

	Technology	View (Y/N)	Maintenance	form	cost	comments
	Proposed – meta- material coatings	Y	None in double pane	Thin-film glass coating	\$3/ft ²	Novel approach/potential for thermal management
(a)	Light Shelves	Ν	High	0		available – specific design per window
(b)	Prismatic Panels	Ν	Alone - High None if in double pane	Sheet or thick plastic panel	\$19/ft ²	
(c)	Louvers/Mirrored Blinds	Y- partially obstructed	High	Blinds	\$35/ft ²	available
(d)	Sun directing glass	Ν	None if in double pane	Thick plastic panel	\$19/ft ²	
(e)	Laser-cut panels	Y- partially obstructed	None	Monolithic glass	\$9-12/ft ²	Fragility issues
(f)	Light pipes	Ν	None	Bulky tubes/fibers	High cost	Specific design per space and high installation costs
	Glass block	Ν	None	Thick glass wall	\$16/ft ²	High installation cost




Energy Efficiency & Renewable Energy

Subwavelength Structures:

- Basic unit for redirecting coating is an oriented anisotropic metal nanoshell

 <u>– light redirection based on structure orientation</u>
- Based on Open Ring Resonator (ORR) metamaterial design and work by Halas group*
- Coating consists of close-packed array of single orientation nanoshells
- Multiple shapes possible hemisphere, half-cylinder, others.




Mirin, et al., Light-bending nanoparticles. Nano Letters (2009) 1255.

Approach – White Light Response

Energy Efficiency & **Renewable Energy**


Resonance Effects:

- ORR structures have a size dependent resonance ۲
- Solution is to fabricate multi-size array via template
- IR response is also possible ${\color{black}\bullet}$



Redirected light

Multi-sized spherical template



Scattering Response 0.8 Amav Scattered Intensity 10 nm 20 nm 0.6 30 nm 40 nm 0.4 0.2 Visible liaht 0.0 0.20.40.81.01.2 1.4 1.6 0.6 Wavelength (µm)

U.S. DEPARTMENT OF

ENERGY

Approach – Coating Fabrication and Scalability


U.S. DEPARTMENT OF Energy ENERGY Renew

Energy Efficiency & Renewable Energy

Fabrication and Scalability

- Metallic shells fabricated via sputter deposition on nanoscale templates
- Current lab-scale 2-3" samples
- PNNL has considered several potential routes to large scale template and metal coatings
- Discussions with industry to determine path forward

Template deposition



100 nm

8 | Building Technologies Office

Approach – Modeling & Optical Measurements


Modeling:

- FDTD numerical modeling gives near field transmission & farfield light redirection
- Allows rapid evaluation of fabrication parameters
 - Thickness, size, orientation, metal, wavelength, angle of incidence

Measurements:


- Performance is evaluated vs. baseline flat coatings
- Coatings are evaluated as a function of:
 - Wavelength
 - Incident angle
 - Polarization
- Microspectrophotometer used for rapid testing and defect analysis

Measurement setup



Microspectrophotometer







Accomplishments: PNNL has demonstrated proof-ofconcept light redirection and broad wavelength response from the sub-wavelength coatings for daylighting. PNNL is currently working on improved performance.

- Progress on Goals: PNNL's progress is well aligned with the project goals & path to commercialization:
- A Demonstrate proof-of-concept (FY12)
- B Demonstrate improved performance (FY13)
- C Demonstrate low-cost scale-up feasibility/durability (FY14,15)
- Awards/Recognition: This work has been reported on at NFRC and DOE workshops. Provisional patents have been filed and a publication has been submitted.


Accomplishments and Progress


U.S. DEPARTMENT OF


Energy Efficiency & Renewable Energy

 Proof-of-concept: single wavelength light redirection from sub-wavelength structure

Schematic and SEM of sub-wavelength structure








Proof-of-concept: Broad Single size structure Multiple size structure 1100 1100 wavelength response Redirection 1000 1000 region Redirection Navelength (nm) Wavelength (nm) 900 900 region 800 800 700 700 600 600 Redirection 500 500 region 400 400 -50 -50 50 50 0 0 Multiple size template Angle (deg) Angle (deg)

11 | Building Technologies Office

Accomplishments and Progress – Modeling

- Modeling shows that light is redirected to shallower angles
- Up to 70% light redirection for a single wavelength structure



Note: this is for a single wavelength structure. Full visible spectrum response improvement is possible with multiple size structures

ENERGY Energy Efficiency & Renewable Energy

Performance

- PNNL has made significant progress to date on the R&D challenges
- The path forward to improving coating performance is:
 - Significantly reduce film defects
 - Improve metal shell conductivity
 - Increase shell packing density, option for multiple layers
 - Optimize design parameters (tilt, thickness, metal choice)
- Color mixing and view have been considered with no show-stoppers

Scale-up & Cost

- PNNL has identified potential manufacturing processes and routes to scale up
- PNNL has also done preliminary cost analysis
- In process of establishing CRADA with PPG Industries
- Future work will focus on these aspects



Project start date: October 2010 Project planned completion date: September 2015 FY12 Milestones – completed FY13 Milestones – in progress

- Modeling guide on Fabrication parameter for optimal performance end Q3
- 10% light redirection over 30% of visible range end Q4
- Report on scalability end Q4

Summary					Legend						
					_	Work co	mpleted				
						Active T	ask				
						Milesto	nes & De	liverable	es (Origir	nal Plan)	
						Milesto	nes & De	liverable	es (Actua	al)	
	FY2	012			FY2	013			FY2	2014	
1 (Octt-Dec)	2 (Jan-Mar)	3 (Apr-Jun)	4 (Jul-Sep)	1 (Octt-Dec)	2 (Jan-Mar)	3 (Apr-Jun)	4 (Jul-Sep)	1 (Octt-Dec)	2 (Jan-Mar)	3 (Apr-Jun)	Q4 (Jul-Sep)
a	α	a	a	o a	- a	a	α	a			
ntal)											
		Q1 (Octt-Dec)		Q1 (Octt-Dec)	Q1 (Octt-Dec) Q2 (Jan-Mar) Q3 (Apr-Jun) Q4 (Jul-Sep) Q4 (Jul-Sep)	FY2012 FY2012 FY2012 (Octt-Dec) G3 (Abr-1nu) G3 (Abr-1nu) G3 (Abr-1nu) G3 (Jau-War) G3 (Jau-War) G4 (Jau-War) G3 (Jau-War) G4 (Jau-	Active T Milesto FY2012 FY2013 FY2013 Gamma Gama </td <td>FY2012 FY2013 FY2012 FY2013 Image: Second second</td> <td>Work completed Active Task Milestones & Deliverable Milestones & Deliverable FY2012 FY2013 FY2013 Image: Strategy of the strategy of</td> <td>Work completed Active Task Milestones & Deliverables (Origin Milestones & Deliverables (Actual FY2012 FY2013 FY2012 FY2013 FY2013 FY2 (add 101-26d) (add 101-26d) Milestones & Deliverables (Actual (add 101-26d) (add 101-26d) Milestones & Deliverables (Actual (add 101-26d) (add 101-26d) <td< td=""><td>Work completed Active Task Milestones & Deliverables (Original Plan) Milestones & Deliverables (Actual) FY2012 FY2013 FY2014 G1 (Octt-Dec) Value Value</td></td<></td>	FY2012 FY2013 FY2012 FY2013 Image: Second	Work completed Active Task Milestones & Deliverable Milestones & Deliverable FY2012 FY2013 FY2013 Image: Strategy of the strategy of	Work completed Active Task Milestones & Deliverables (Origin Milestones & Deliverables (Actual FY2012 FY2013 FY2012 FY2013 FY2013 FY2 (add 101-26d) (add 101-26d) Milestones & Deliverables (Actual (add 101-26d) (add 101-26d) Milestones & Deliverables (Actual (add 101-26d) (add 101-26d) (add 101-26d) (add 101-26d) <td< td=""><td>Work completed Active Task Milestones & Deliverables (Original Plan) Milestones & Deliverables (Actual) FY2012 FY2013 FY2014 G1 (Octt-Dec) Value Value</td></td<>	Work completed Active Task Milestones & Deliverables (Original Plan) Milestones & Deliverables (Actual) FY2012 FY2013 FY2014 G1 (Octt-Dec) Value Value

ENERGY Energy Efficiency & Renewable Energy

Project Budget: Project start FY11 (Scoping study, \$100K), FY12 (technical feasibility, \$100K), FY13 (Enhance Performance, \$250K)

- Variances: No variances to date
- Cost to Date: FY11- \$100K, FY12 \$100K, FY13 \$90K to date

Additional Funding: Working on establishing CRADA in FY13 with PPG industries.

Budget History										
FY2011		FY2	2012	FY2013						
DOE	Cost-share	DOE	Cost-share	DOE	Cost-share					
\$100K	\$0K	\$100K	\$0K	\$250K	\$0K					

U.S. DEPARTMENT OF

Energy Efficiency & Renewable Energy

Partners, Subcontractors, and Collaborators: PNNL has been consulting with PPG industries about the technology and is in discussions for a CRADA on future work.

Technology Transfer, Deployment, Market Impact: PNNL will address the lab-scale R&D challenges and partner with industry to address cost, scale-up, and other factors. The successful technology will be licensed to an appropriate manufacturer.

Communications:

- Nanolens Scoping Study Report (DOE, 2011) identify potential market impact
- Nanolens R&D roadmap Report (DOE, 2012) outline R&D path to market
- NFRC Presentation (Dr. Phelan, 2012)
- DOE Windows Roadmap Workshop Presentation (Dr. Gaspar, 2012)
- Journal Article Submitted (Dr. Alvine, 2013) technological results

Next Steps and Future Plans:

- Improve broad-band light redirection performance to 10% (FY13), then to 30-60% (FY14)
- Establish CRADA with PPG industries (FY13)
- Intermediate scale-up demonstration (FY14)
- Durability testing for lifetime assessment (FY15)
- Refine materials/process selection based on cost analysis (FY15)